City of Benson
City Council Communication

Special Meeting **November 13, 2017**

To: Mayor and Council Agenda Item # 8

From: Bradley J. Hamilton, P.E.,
Public Works Director / City Engineer

Subject:

Discussion and possible action regarding the Procurement of Environmental Remediation Services for Ocotillo Avenue Sewer for the removal of regulated Asbestos Sewer pipe under AZ State Contract # ADEQ17-140223 for $22,181.00

Discussion:

The City needs to replace about 600' feet of sewer line along Ocotillo Avenue across the street from Tractor Supply. The current pipe is failing and needs to be replaced. The current pipe is made with Cement Asbestos and needs to be properly disposed of. City Crews will do all the excavation and replacement of the pipe. Southwest Hazard Control Inc. will remove and dispose of the pipe.

This project is in the budget under CIP WW 10-1.

Staff Recommendation:

Approval of the Procurement of Environmental Remediation Services for Ocotillo Avenue Sewer for the removal of regulated Asbestos Sewer pipe under AZ State Contract # ADEQ17-140223 for $22,181.00

SHC

Solving Environmental Concerns Efficiently, Effectively & Ethically

10/19/ 2017

City of Benson
Attn: Bradley Hamilton

RE: Sewer Pipe 600LF
Benson, AZ. 85602

Subject: Transite Pipe

Bradley,
Per your request for a quotation at the address listed above, we appreciate the opportunity to possibly assist in your renovation project.
Southwest HAZARD CONTROL, Inc. Will furnish Labor, Materials, Equipment, cutting, Disposal, and encapsulation on broken pieces of "Asbestos Cement Pipe(transite), from an area of approximately 600 linear feet of 8" pipe located in Benson, including the following:

- *Mobilization - Monday thru Friday 7am to 4pm*
- *AHERA trained contractor Supervisor and tech's*
- Clean-up and Disposal to comply with Federal, State, and Local Requirements.
- *Removal wet method with amended water during loading of Cement pipe (Transite). SDS furnished upon request.*
- *Load and dispose with completed manifest for owner.*
- *SHC will encapsulate broken ends of transite pipe and double bag 6 mil poly loose pieces.*
- Manifesting provided to Owner upon completion- Landfill facilities- RAD Landfill- Florence, AZ.
- Materials are considered Category II- Non Friable.
- OSHA required personal sampling included- as required for Asbestos Work.

Cost for Cement Pipe (transite).

TOTAL COST - $ 22,181.00

Add: $1,848.43 per additional day after 12days

Notes:

- 1. Insurance Certificate
- 2. Water and Power supplied by SHC
- 3. Material tax paid for at the time of purchase.
- 4. City of Benson will excavate material and expose pipe for SHC to remove.

Acceptance of Proposal
The above prices and conditions are satisfactory and are hereby accepted. Please sign and fax to 520-622-3643 to authorize the work.

Signature _____ Date _____.

SHC

Solving Environmental Concerns Efficiently, Effectively & Ethically

Should you have any questions please feel free to contact me at your convenience.

Sincerely;

Mitchell D. Kring
Southwest Hazard Control, Inc.
Office - (520) 622-3607
Cell - (520) 305-6461